Format for Estimate

Date.....

			Daic	
Sl. No.	Specification	Qty.	Rate Rs.	Amount Rs.
1.	Dismantling- Dismantling two inside palla, existing partition repair.			
2.	Cash counter - 2 pcs 4 ⁱ 10 ⁱⁱ x2 ⁱ 0 ⁱⁱ x3 ⁱ 10 ⁱⁱ Made of 19mm Green ply,6 mm ply, outside branded laminates, necessary lock,handle,chanel,hinges inside paint as per approved design	40 Sq.ft.		
3.	File rack — 2 pcs 4 ⁱ 0 ⁱⁱ x4 ⁱ 0 ⁱⁱ x1 ⁱ 5 ⁱⁱ Made of 19mm Green ply,6 mm ply, outside branded laminates, necessary lock,handle,chanel,hinges inside paint as per approved design	32 Sq.ft.		
4.	$\frac{\textbf{Paneling}}{4^{i}0^{ii} \times 6^{ii} \times 1^{i}6^{ii}} - 2 \text{ pcs}$	12 Sq.ft.		
5.	Made of ^{19mm} Green ply,6 mm ply, outside branded laminates, as per approved design.	40 Sq.ft.		
6.	6 mm clear glass fix with aluminium chanel or wood frame	17.5 Sq.ft.		
	Bursar table- 4 ⁱ 0 ⁱⁱ x2 ⁱ 0 ⁱⁱ x2 ⁱ 6 ⁱⁱ ; 3 ⁱ 0 ⁱⁱ x1 ⁱ 6 ⁱⁱ x2 ⁱ 6 ⁱⁱ Made of 19mm Green ply,6 mm ply, outside branded laminates, necessary lock,handle,chanel,hinges inside paint as per approved	17.5 Sq.it.		
7.	File rack (southside wall) 2 ⁱ 0 ⁱⁱ x7 ⁱ 0 ⁱⁱ x1 ⁱ 6 ⁱⁱ	14 Sq.ft.		
	Made of 19mm Green ply,6 mm ply, outside branded laminates, necessary lock,handle,chanel,hinges inside paint as per approved design			